BRUHAT BENGALURU MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Footpaths in cross roads of Kodigehalli in Ward No.12,Kodigehalli .

Sl. No.	Quantity.	Description	Unit	Rates Quotation by Sri V. Punuswamy	
				In Figures	In Words
1	462.50	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	168.39	Rupees One Hundred Sixty Eight And Paise Thirty Nine Only
2	0.00	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using	Cum	0.00	Rupees Nil
3	0.00	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure /Superstructure complete as per Drawing and Technical Specifications.	Ton	0.00	Rupees Nil
4	756.00	Removing and resetting of Footpath Slab and painting in C.M.1:3 (approved Rate).	sqm	193.40	Rupees One Hundred Ninety Three And Paise Forty Only
5	189.00	Providing B.S.slabs of selected quality roughly dressed having a size of 10cms thick and fixed is cement mortor (1:6) including fixing curing etc.complete.as directed by the Enginer in charge of the work (excluding GST and Area Leading Charges) (approved Rate).	sqm	688.85	Rupees Six Hundred Eighty Eight And Paise Eighty Five Only

V. Punu

Signature of the Contractor

Executive Engineer

Sl.	Quantity.	Description	Unit	Rates Quotation by Sri V. Punuswamy	
				In Figures	In Words
6	290.25	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications.	sqm	1036.57	Rupees One Thousand Thirty Six And Paise Fifty Seven Only
7	354.75	Removing and resetting of cobble stones (approved Rate).	sqm	312.74	Rupees Three Hundred Twelve And Paise Seventy Four Only
8	264.00	Removing and resetting of Kerb stone painting in C.M.1:3 (approved Rate).	Nos	97.11	Rupees Ninety Seven And Paise Eleven Only
9	119.60	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)	Cum	5207.20	Rupees Five Thousand Two Hundred Seven And Paise Twenty Only
10	124.50	Providing and fixing pre cast solid cement concrete kerb stones made out of CC M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete	sqm	417.26	Rupees Four Hundred Seventeen And Paise Twenty Six Only
	713.28	Qty above 125%		343.40	Rupees Three Hundred Forty Three And Paise Forty Only
11	339.50	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	sqm	76.95	Rupees Seventy Six And Paise Ninety Five Only
12	462.50	Cost of Haulage excluding Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum.10km=100t.km. (Tipper 5.5 m3)	Cum	86.91	Rupees Eighty Six And Paise Ninety One Only
		EIRL			

V. Ramu

Signature of the Contractor

Executive Engineer

Sl.	Quantity.	Description	Unit	Rates Quotation by Sri V. Punuswamy	
				In Figures	In Words
E1	160.40	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	sqm	965.95	Rupees Nine Hundred Sixty Five And Paise Ninety Five Only
E2	91.80	Supplying and fixing Pre cast reinforced concrete slab 10cm thick including cost of rinforcement as per design and drawing courses cost of all materials, labour complete as per specifications. Specification	sqm	1705.25	Rupees One Thousand Seven Hundred Five And Paise Twenty Five Only

V. Punu

Signture of the Contractor

Executive Engineer
Byatarayanapura Division

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು